BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-06

Name of Work:-Providing Rainwater harvesting at Yelahanka old town Bangla school and venkatala Govt School in kempegowda ward no-01

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri THEJESH N (S J CONSTRUCTIONS)	
				Rate	Rate in Words
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ SR 2018-19	Cum	97.85	125.00	Rupees One Hundred Twenty Five Only
2	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19	Cum	55.79	280.00	Rupees Two Hundred Eighty Only
3	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	153.64	75.00	Rupees Seventy Five Only
4	KSRB 2.8 : Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. Specification. No. KBS, No. 6/ Item No. 2.15/ PWD SR 2018-19	Cum	18.90	2200.00	Rupees Two Thousand Two Hundred Only
5	KSRB 5.2-2 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with mud mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 22/ Item No. 5.5/ SR 2018-19	Cum	6.02	4300.00	Rupees Four Thousand Three Hundred Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri THEJESH N (S J CONSTRUCTIONS)	
				Rate	Rate in Words
6	RCC Pipe NP 2 1200 mm dia including collers Page No XII Sl No 594 code 0830 SR 2018-19	Mtrs	3.00	4000.00	Rupees Four Thousand Only
7	RCC Precast covering slab for drain (10cm thick)	sqm	35.65	2100.00	Rupees Two Thousand One Hundred Only
8	0750 - Supply and Providing Aggregate 40 mm and below SR 2018-19 (P.II / SL No 25)	Cum	15.22	1000.00	Rupees One Thousand Only
9	0749 - Supply and Providing Aggregate 20 mm and below SR 2018-19 (P.II / SL no 28)	Cum	23.87	1000.00	Rupees One Thousand Only
10	0731 - Supply and Providing Sand PWD SR 2018-19 (P.III / SR No 51	Cum	3.39	1500.00	Rupees One Thousand Five Hundred Only
11	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications, MORTH specifications No. 408, (P.No.13, I.No.4-1.2 of PW,P&IWTD S.R 2018-19)	Cum	2.09	5000.00	Rupees Five Thousand Only
12	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 26/ Item No. 5.27/ PWD SR 2018-19	sqm	159.00	899.00	Rupees Eight Hundred Ninety Nine Only
13	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 Page No. 31/ Item No. 7.9/ PWD SR 2018-19	Kgs	7.00	97.00	Rupees Ninety Seven Only
14	Man hole cover 24" x 24" Page No XXXII Sr 2018-19	Nos	3.00	2300.00	Rupees Two Thousand Three Hundred Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.